					ST DEPARTMENT DIVISION O	OF NA					AMEI	FC NDED REPC	RM 3		
		APP	LICATION	FOR P	PERMIT TO DRILL	-	1. WELL NAME and NUMBER GMBU H-32-8-18								
2. TYPE C		RILL NEW WELL ((	REENT	ER P&A	WELL DEEPE	N WELL	3. FIELD OR WILDCAT EIGHT MILE FLAT								
4. TYPE C		Oil			I Methane Well: NO			5. UNIT or COMMUNITIZATION AGREEMENT NAME  GMBU (GRRV)						NAME	
6. NAME	OF OPERATOR	2			TION COMPANY					7. OPERATOR PHONE					
8. ADDRE	SS OF OPERA				ton, UT, 84052					435 646-4825  9. OPERATOR E-MAIL mcrozier@newfield.com					
	RAL LEASE NO		RC 3 Box 305	1	11. MINERAL OWNE	400		<u> </u>		12. SURFACE OWN	ERSHIP		_		
		ML-22058 OWNER (if box 1	12 = 'fee')		FEDERAL IND	IAN (	) STATE (	PEE (		FEDERAL IN  14. SURFACE OWN	DIAN (	~	900	FEE ()	
		ACE OWNER (if b		'\						16. SURFACE OWN					
151 ADDI		AGE GWAEK (II D	0x 12 = 100		10 INTEND TO COM	MINICI	E DDODUCT	TON EDOM		19. SLANT		112 (11 50)			
	AN ALLOTTEE 2 = 'INDIAN')	OR TRIBE NAME		ľ	18. INTEND TO COM MULTIPLE FORMATI YES (Submit C	IONS	gling Applicat		_	_	RECTION	IAL (B)	HORIZON	ITAL 👝	
20 100	ATION OF WE				TAGES		R-QTR	SECTI		TOWNSHIP		ANGE	_	RIDIAN	
	ON AT SURFAC		6		1835 FEL	_	IWNE	32		8.0 S	_	.8.0 E		S	
Top of U	ppermost Pro	ducing Zone	11	.84 FNL	 _ 2276 FEL	N	IWNE	32		8.0 S	1	.8.0 E		S	
At Total	Depth		15	98 FNL	. 2618 FWL	9	SENW	32		8.0 S	1	.8.0 E		S	
21. COUN	ITY	UINTAH		2	22. DISTANCE TO N		T LEASE LIN	IE (Feet)		23. NUMBER OF AC		DRILLING 20	UNIT		
					25. DISTANCE TO N (Applied For Drilling	g or Co	mpleted)	SAME POOL	-	26. PROPOSED DEI	PTH :: 6557	TVD: 64:	20		
27. ELEV	ATION - GROU	JND LEVEL		-	28. BOND NUMBER	14	190	29. SOURCE OF DRILLING WATER /							
		4977				B00	01834 WATER RIGHTS APPROVAL NUMBER IF APPLICABLE					LICABLE			
					Hole, Casing,				1	_					
String	Hole Size	Casing Size 8.625	0 - 300	Weig 24	_					Yield 1.17	Weight 15.8				
PROD	7.875	5.5	0 - 6557	15			8.3					3.26	11.0		
										50/50 Poz		363	1.24	14.3	
					A	ТТАСН	IMENTS								
	VERIFY T	HE FOLLOWIN	G ARE ATT	ACHE	D IN ACCORDAN	CE WI	TH THE U	TAH OIL	AND G	SAS CONSERVATI	ON GE	NERAL F	RULES		
<b>w</b> w	ELL PLAT OR	MAP PREPARED E	BY LICENSED	SURV	EYOR OR ENGINEE	R	СОМ	IPLETE DRI	ILLING	PLAN					
AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)							FOR	м 5. IF ОРІ	ERATOI	R IS OTHER THAN T	HE LEAS	SE OWNER	<b>.</b>		
DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)								OGRAPHIC	AL MAI	•					
NAME Mandie Crozier TITLE Regulatory Tech									PHO	<b>NE</b> 435 646-4825					
SIGNATURE   DATE 08/16/2011									EMAI	<b>L</b> mcrozier@newfield	.com				
	iber assign )4751878(				APPROVAL				B	al Gillian State of the Control of t					
									r	Anni ivianagei					

# NEWFIELD PRODUCTION COMPANY GMBU H-32-8-18 AT SURFACE: NW/NE SECTION 32, T8S, R18E UINTAH COUNTY, UTAH

#### TEN POINT DRILLING PROGRAM

#### 1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

#### 2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

 Uinta
 0' – 1650'

 Green River
 1650'

 Wasatch
 6280'

 Proposed TD
 6557'

#### 3. <u>ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:</u>

Green River Formation (Oil) 1650' – 6280'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval Date Sampled Flow Rate Temperature

Hardness pH

Water Classification (State of Utah)

Dissolved Calcium (Ca) (mg/l)

Dissolved Iron (Fe) (ug/l)

Dissolved Sodium (Na) (mg/l)

Dissolved Carbonate (CO<sub>3</sub>) (mg/l)

Dissolved Bicarbonate (NaHCO<sub>3</sub>) (mg/l)

Dissolved Sulfate (SO<sub>4</sub>) (mg/l)

Dissolved Total Solids (TDS) (mg/l)

#### 4. PROPOSED CASING PROGRAM

a. Casing Design: GMBU H-32-8-18

Size	Interval		Weight	Grade	Coupling	Design Factors			
Size	Тор	Bottom	weigni	Grade	Coupling	Burst	Collapse	Tension	
Surface casing	0'	300'	24.0	J-55	STC	2,950	1,370	244,000	
8-5/8"	U	300	24.0	0-55	310	17.53	14.35	33.89	
Prod casing	2	0.5571	45.5	1.55	1.70	4,810	4,040	217,000	
5-1/2"	0'	6,557'	15.5	J-55	LTC	2.31	1.94	2.14	

#### Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
Pore pressure at surface casing shoe = 8.33 ppg
Pore pressure at prod casing shoe = 8.33 ppg
Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: GMBU H-32-8-18

Job	Fill	Description	Sacks ft <sup>3</sup>	OH Excess*	Weight (ppg)	Yield (ft <sup>3</sup> /sk)	
			138		W 1 07	,	
Surface casing	300'	Class G w/ 2% CaCl	130	30%	15.8	1.17	
			161				
Prod casing	4,557'	Prem Lite II w/ 10% gel + 3%	315	30%	11.0	3.26	
Lead	4,557	KCI	1026	30%	11.0	3.20	
Prod casing	2,000'	50/50 Poz w/ 2% gel + 3%	363	30%	14.3	1.24	
Tail	2,000	KCI	451	30%	14.3	1.24	

<sup>\*</sup>Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

#### 5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit** C for a diagram of BOP equipment that will be used on this well.

#### 6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

From surface to  $\pm 300$  feet will be drilled with an air/mist system. The air rig is equipped with a 6 ½" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about  $\pm 300$  feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

#### 7. <u>AUXILIARY SAFETY EQUIPMENT TO BE USED</u>:

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

#### 8. <u>TESTING, LOGGING AND CORING PROGRAMS</u>:

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +-. A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

#### 9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

# 10. <u>ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:</u>

It is anticipated that the drilling operations will commence the fourth quarter of 2011, and take approximately seven (7) days from spud to rig release.

#### T8S, R18E, S.L.B.&M. S89\*56'W - 79.96 G.L.O. S88°52'44"W - 2633.36' (Meas.) S88°56'13"W - 2658.82' (Meas.) 1910 1910 Brass Cap Brass Spike Top of Cap Hole ' (Meas.) 1835 15, 2645. 2489 2800 Center of NO1.03'16"W 2618 Pattern Bottom of Hole (G.L.O.) Brass Cap N0.03'W Set Stone N0.03,W Pile of Rocks WELL LOCATION: H-32-8-18ELEV. EXIST. GRADED GROUND = 4977' 10, W... 25,65.00N Corner Proportioned Brass Cap 1910 (Not Set) Brass Cap N89°01'27"E - 2644.19' (Meas.) N89°01'27"E - 2644.19' (Meas.) N89'59'E (G.L.O.) = SECTION CORNERS LOCATED H-32-8-18BASIS OF ELEV: Elevations are based on (Surface Location) NAD 83 an N.G.S. OPUS Correction. LOCATION: $LATITUDE = 40^{\circ} 04' 47.34''$ LAT. 40°04'09.56" LONG. 110°00'43.28" LONGITUDE = 109° 54' 52.14" (Tristate Aluminum Cap) Elev. 5281.57'

# NEWFIELD EXPLORATION COMPANY


WELL LOCATION, H-32-8-18, LOCATED AS SHOWN IN THE NW 1/4 NE 1/4 OF SECTION 32, T8S, R18E, S.L.B.&M. UINTAH COUNTY, UTAH.

TARGET BOTTOM HOLE, H-32-8-18, LOCATED AS SHOWN IN THE SE 1/4 NW 1/4 OF SECTION 32, T8S, R18E, S.L.B.&M. UINTAH COUNTY, UTAH.



#### NOTES:


- 1. Well footages are measured at right angles to the Section Lines.
- 2. Bearings are based on Global Positioning Satellite observations.





# TRI STATE LAND SURVEYING & CONSULTING


180 NORTH VERNAL AVE. – VERNAL, UTAH 84078 (435) 781–2501

	( ) /	
DATE SURVEYED: 06-21-11	SURVEYED BY: K.S.	VERSION:
DATE DRAWN: 08-05-11	DRAWN BY: F.T.M.	\/1
REVISED:	SCALE: 1" - 1000'	VI











# **NEWFIELD EXPLORATION**

USGS Myton SW (UT) SECTION 32 T8, R18 H-32-8-18

Wellbore #1

Plan: Design #1

# **Standard Planning Report**

21 July, 2011





# PayZone Directional Services, LLC.

Planning Report



EDM 2003.21 Single User Db Database: Company: **NEWFIELD EXPLORATION** Project: USGS Myton SW (UT) **SECTION 32 T8, R18** Site:

Well: H-32-8-18 Wellbore: Wellbore #1 Design: Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well H-32-8-18

H-32-8-18 @ 4989.0ft (Newfield Rig) H-32-8-18 @ 4989.0ft (Newfield Rig)

Minimum Curvature

USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA Project

US State Plane 1983 Map System: North American Datum 1983

Geo Datum:

Map Zone: **Utah Central Zone** 

Mean Sea Level System Datum:

Site **SECTION 32 T8, R18** 

Northing: 7,206,399.39 ft 40° 4' 35.740 N Site Position: Latitude: Lat/Long Easting: 2,339,885.33 ft 109° 0' 0.000 W From: Longitude: **Position Uncertainty:** 0.0 ft Slot Radius: **Grid Convergence:** 1.60 °

H-32-8-18, SHL LAT: 40 04 47.34 LONG: -109 54 52.14 Well

**Well Position** +N/-S -134.4 ft Northing: 7,201,729.21 ft Latitude: 40° 4' 47.340 N +E/-W -255,890.3 ft 2,084,038.08 ft 109° 54' 52.140 W Easting: Longitude:

**Position Uncertainty** 0.0 ft Wellhead Elevation: 4,989.0 ft **Ground Level:** 4,977.0 ft

Wellbore #1 Wellbore Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (°) (°) (nT) 65.85 IGRF2010 2011/07/21 11.25 52,305

Design	Design #1					
Audit Notes:						
Version:		Phase:	PROTOTYPE	Tie On Depth:	0.0	
Vertical Section:		Depth From (TVD)	+N/-S	+E/-W	Direction	
		(ft)	(ft)	(ft)	(°)	
		5,250.0	0.0	0.0	221.44	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,463.9	12.96	221.44	1,456.5	-72.9	-64.4	1.50	1.50	0.00	221.44	
5,356.5	12.96	221.44	5,250.0	-727.3	-642.1	0.00	0.00	0.00	0.00	H-32-8-18 TGT
6,557.0	12.96	221.44	6,420.0	-929.1	-820.2	0.00	0.00	0.00	0.00	



# PayZone Directional Services, LLC.

Planning Report



Database:EDM 2003.21 Single User DbCompany:NEWFIELD EXPLORATIONProject:USGS Myton SW (UT)Site:SECTION 32 T8, R18

Well: H-32-8-18
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well H-32-8-18

H-32-8-18 @ 4989.0ft (Newfield Rig) H-32-8-18 @ 4989.0ft (Newfield Rig)

True

Minimum Curvature

ign:	Design #1								
nned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
Start Build									
700.0	1.50	221.44	700.0	-1.0	-0.9	1.3	1.50	1.50	0.00
800.0	3.00	221.44	799.9	-3.9	-3.5	5.2	1.50	1.50	0.00
900.0	4.50	221.44	899.7	-8.8	-7.8	11.8	1.50	1.50	0.00
1,000.0	6.00	221.44	999.3	-15.7	-13.8	20.9	1.50	1.50	0.00
1,100.0	7.50	221.44	1,098.6	-13.7 -24.5	-13.6	32.7	1.50	1.50	0.00
1,100.0	9.00	221. <del>44</del> 221.44		-24.5 -35.3	-21.0 -31.1	32.7 47.0			0.00
1,200.0		221.44 221.44	1,197.5	-35.3 -47.9	-31.1 -42.3		1.50	1.50 1.50	
	10.50	221.44 221.44	1,296.1	-47.9 -62.6	-42.3 -55.2	64.0	1.50	1.50 1.50	0.00
1,400.0	12.00	221.44	1,394.2	-0∠.0	-55.2	83.5	1.50	1.50	0.00
1,463.9	12.96	221.44	1,456.5	-72.9	-64.4	97.3	1.50	1.50	0.00
Start 3892.0	6 hold at 1463.9 N	/ID							
1,500.0	12.96	221.44	1,491.7	-79.0	-69.7	105.4	0.00	0.00	0.00
1,600.0	12.96	221.44	1,589.2	-95.8	-84.6	127.8	0.00	0.00	0.00
1,700.0	12.96	221.44	1,686.6	-112.6	-99.4	150.2	0.00	0.00	0.00
1,800.0	12.96	221.44	1,784.1	-129.4	-114.3	172.6	0.00	0.00	0.00
1,900.0	12.96	221.44	1,881.5	-146.2	-129.1	195.1	0.00	0.00	0.00
2,000.0	12.96	221.44	1,979.0	-163.0	-143.9	217.5	0.00	0.00	0.00
2,100.0	12.96	221.44	2,076.5	-179.9	-158.8	239.9	0.00	0.00	0.00
2,200.0	12.96	221.44	2,173.9	-196.7	-173.6	262.3	0.00	0.00	0.00
2,300.0	12.96	221.44	2,271.4	-213.5	-188.5	284.8	0.00	0.00	0.00
2,400.0	12.96	221.44	2,368.8	-230.3	-203.3	307.2	0.00	0.00	0.00
2,500.0	12.96	221.44	2,466.3	-247.1	-218.1	329.6	0.00	0.00	0.00
2,600.0	12.96	221.44	2,563.7	-263.9	-233.0	352.0	0.00	0.00	0.00
2,700.0	12.96	221.44	2,661.2	-280.7	-247.8	374.5	0.00	0.00	0.00
2,800.0	12.96	221.44	2,758.6	-297.5	-262.7	396.9	0.00	0.00	0.00
2,900.0	12.96	221.44	2,856.1	-314.3	-277.5	419.3	0.00	0.00	0.00
3,000.0	12.96	221.44	2,953.5	-314.3	-277.3	441.7	0.00	0.00	0.00
3,100.0	12.96	221.44	3,051.0	-347.9	-307.2	464.1	0.00	0.00	0.00
3,200.0	12.96	221.44	3,148.4	-347.9 -364.8	-322.0	486.6	0.00	0.00	0.00
3,300.0	12.96	221. <del>44</del> 221.44	3,146.4 3,245.9	-304.6 -381.6	-322.0 -336.9	509.0	0.00	0.00	0.00
3,400.0	12.96	221.44	3,343.4	-398.4	-351.7	531.4	0.00	0.00	0.00
3,500.0		221.44	3,440.8	-415.2	-366.6	553.8	0.00	0.00	0.00
3,600.0	12.96	221.44	3,538.3	-432.0	-381.4	576.3	0.00	0.00	0.00
3,700.0	12.96	221.44	3,635.7	-448.8	-396.2	598.7	0.00	0.00	0.00
3,800.0	12.96	221.44	3,733.2	-465.6	-411.1	621.1	0.00	0.00	0.00
3,900.0	12.96	221.44	3,830.6	-482.4	-425.9	643.5	0.00	0.00	0.00
4,000.0	12.96	221.44	3,928.1	-499.2	-440.8	666.0	0.00	0.00	0.00
4,100.0	12.96	221.44	4,025.5	-516.0	-455.6	688.4	0.00	0.00	0.00
4,200.0	12.96	221.44	4,123.0	-532.9	-470.4	710.8	0.00	0.00	0.00
4,300.0	12.96	221.44	4,220.4	-549.7	-485.3	733.2	0.00	0.00	0.00
4,400.0			4,317.9	-566.5				0.00	0.00
4,400.0	12.96	221.44			-500.1 -515.0	755.7	0.00	0.00	
4,500.0	12.96	221.44	4,415.3	-583.3	-515.0 -529.8	778.1	0.00		0.00
	12.96	221.44	4,512.8	-600.1		800.5	0.00	0.00	0.00
4,700.0	12.96	221.44	4,610.2	-616.9	-544.6	822.9	0.00	0.00	0.00
4,800.0	12.96	221.44	4,707.7	-633.7	-559.5	845.3	0.00	0.00	0.00
4,900.0	12.96	221.44	4,805.2	-650.5	-574.3	867.8	0.00	0.00	0.00
5,000.0	12.96	221.44	4,902.6	-667.3	-589.2	890.2	0.00	0.00	0.00



# PayZone Directional Services, LLC.

Planning Report



Database: EDM 2003.21 Single User Db Company: NEWFIELD EXPLORATION Project: USGS Myton SW (UT) Site: SECTION 32 T8, R18

 Well:
 H-32-8-18

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well H-32-8-18

H-32-8-18 @ 4989.0ft (Newfield Rig) H-32-8-18 @ 4989.0ft (Newfield Rig)

True

Minimum Curvature

nned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,100.0 5,200.0 5,300.0	12.96 12.96 12.96	221.44 221.44 221.44	5,000.1 5,097.5 5,195.0	-684.1 -701.0 -717.8	-604.0 -618.8 -633.7	912.6 935.0 957.5	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
5,356.5	12.96	221.44	5,250.0	-727.3	-642.1	970.1	0.00	0.00	0.00
Start 1200.6	hold at 5356.5 N	ID							
5,400.0 5,500.0	12.96 12.96	221.44 221.44	5,292.4 5,389.9	-734.6 -751.4	-648.5 -663.4	979.9 1,002.3	0.00 0.00	0.00 0.00	0.00 0.00
5,600.0 5,700.0	12.96 12.96	221.44 221.44	5,487.3 5,584.8	-768.2 -785.0	-678.2 -693.0	1,024.7 1,047.2	0.00 0.00	0.00 0.00	0.00 0.00
5,800.0 5,900.0	12.96 12.96	221.44 221.44	5,682.2 5,779.7	-801.8 -818.6	-707.9 -722.7	1,069.6 1,092.0	0.00 0.00	0.00 0.00	0.00 0.00
6,000.0	12.96	221.44	5,877.1	-835.4	-737.6	1,114.4	0.00	0.00	0.00
6,100.0 6,200.0	12.96 12.96	221.44 221.44	5,974.6 6,072.0	-852.2 -869.1	-752.4 -767.3	1,136.9 1,159.3	0.00 0.00	0.00 0.00	0.00 0.00
6,300.0	12.96	221.44	6,169.5	-885.9	-782.1	1,181.7	0.00	0.00	0.00
6,400.0 6,500.0	12.96 12.96	221.44 221.44	6,267.0 6,364.4	-902.7 -919.5	-796.9 -811.8	1,204.1 1,226.5	0.00 0.00	0.00 0.00	0.00 0.00
6,557.0	12.96	221.44	6,420.0	-929.1	-820.2	1,239.3	0.00	0.00	0.00
TD at 6557.0									

Plan Annotations				
Measured	Vertical	Local Coor	dinates	
Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment
600.0	600.0	0.0	0.0	Start Build 1.50
1,463.9	1,456.5	-72.9	-64.4	Start 3892.6 hold at 1463.9 MD
5,356.5	5,250.0	-727.3	-642.1	Start 1200.6 hold at 5356.5 MD
6,557.0	6,420.0	-929.1	-820.2	TD at 6557.0



Project: USGS Myton SW (UT) Site: SECTION 32 T8, R18


Well: H-32-8-18 Wellbore: Wellbore #1 Design: Design #1


KOP @ 600' DOGLEG RATE 1.5 DEG/100 TARGET RADIUS IS 75'




Azimuths to True North Magnetic North: 11.25°

Magnetic Field Strength: 52304.7snT Dip Angle: 65.85° Date: 2011/07/21 Model: IGRF2010









# SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1463.9	12.96	221.44	1456.5	-72.9	-64.4	1.50	221.44	97.3	
4	5356.5	12.96	221.44	5250.0	-727.3	-642.1	0.00	0.00	970.1	H-32-8-18 TGT
5	6557.0	12.96	221.44	6420.0	-929.1	-820.2	0.00	0.00	1239.3	

# NEWFIELD PRODUCTION COMPANY GMBU H-32-8-18 AT SURFACE: NW/NE SECTION 32, T8S, R18E UINTAH COUNTY, UTAH

#### ONSHORE ORDER NO. 1

#### **MULTI-POINT SURFACE USE & OPERATIONS PLAN**

#### 1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU H-32-8-18 located in the NW 1/4 NE 1/4 Section 32, T8S, R18E, Uintah County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southeasterly – 11.7 miles  $\pm$  to it's junction with an existing road to the northeast; proceed northeasterly – 6.8 miles  $\pm$  to it's junction with an existing road to the northwest; proceed in a northwesterly direction – 0.9 miles  $\pm$  to the existing 31-32-8-18 well pad.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

#### 2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 31-32-8-18 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

# 3. <u>LOCATION OF EXISTING WELLS</u>

Refer to Exhibit "B".

#### 4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

#### 5. LOCATION AND TYPE OF WATER SUPPLY

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District Water Right: 43-10136

Maurice Harvey Pond Water Right: 47-1358

Neil Moon Pond Water Right: 43-11787

Newfield Collector Well

Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy

District).

There will be no water well drilled at this site.

#### 6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

#### 7. METHODS FOR HANDLING WASTE DISPOSAL

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

#### 8. <u>ANCILLARY FACILITIES</u>

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

#### 9. <u>WELL SITE LAYOUT</u>

See attached Location Layout Sheet.

#### **Fencing Requirements**

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

#### 10. PLANS FOR RESTORATION OF SURFACE:

#### a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

### b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

#### 11. <u>SURFACE OWNERSHIP</u> – State of Utah.

#### 11. OTHER ADDITIONAL INFORMATION :

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #01-177, 11/14/01. Paleontological Resource Survey prepared by, Wade Miller, 9/6/11. See attached report cover pages, Exhibit "D".

#### **Surface Flow Line**

Newfield requests 3,541' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. For all new wells, Newfield. **Refer to Topographic Map "C"** for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

<u>Clearing and Grading</u>: No clearing or grading of the ROW will be required. The centerline of the proposed route will be staked prior to installation. Flow lines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated. If necessary, temporary use or construction/storage areas will be identified on a topographic map included in the approved permit.

<u>Installation</u>: The proposed flow lines will be installed 4-6" above the ground. For portions along existing two-track and primary access roads, lengths of pipe will be strung out in the borrow ditch, welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country (not along existing or proposed roads), travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of three (3) inches deep, the soil will be deemed too wet to adequately support the equipment.

<u>Termination and Final Reclamation:</u> After abandonment of the associated production facilities, the flow lines will be cut and removed, and any incidental surface disturbance reclaimed. Reclamation procedures will follow those outlined in the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities

### Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

#### **Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

#### **Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the GMBU H-32-8-18, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU H-32-8-18, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

#### 13. **LESSEE'S OR OPERATOR'S REPRENSENTATIVE AND CERTIFICATION:**

#### Representative

Name: Tim Eaton

Address: Newfield Production Company

Route 3, Box 3630 Myton, UT 84052

Telephone: (435) 646-3721

#### Certification


Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #H-32-8-18, Section 32, Township 8S, Range 18E: Lease ML-22058 Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #B001834.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


9/12/	
Date	Mandie Crozie
	Regulatory Analys
	Newfield Production Company


2-M SYSTEM

Blowout Prevention Equipment Systems



**EXHIBIT C** 








CROSS SECTIONS


31-32-8-18 (Existing Well)


I-32-8-18 (Proposed Well)


H-32-8-18 (Proposed Well)

Pad Location: NWNE Section 32, T8S, R18E, S.L.B.&M.









1'' = 60' STA. 0+45

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards) 6" TOPSOIL CUT FILL **EXCESS** ITEM Topsoil is PAD 160 110 not included in Pad Cut PIT 690 0 690

NOTE: UNLESS OTHERWISE NOTED ALL CUT/FILL SLOPES ARE AT 1.5:1

SURVEYED BY:	K.S.	DATE SURVEYED:	06-21-11	VERSION:
DRAWN BY:	F.T.M.	DATE DRAWN:	08-05-11	\/1
SCALE: 1"	= 60'	REVISED:		V I

50

230

800

TOTALS

850

# NEWFIELD EXPLORATION COMPANY


TYPICAL RIG LAYOUT

31-32-8-18 (Existing Well)

I-32-8-18 (Proposed Well)

H-32-8-18 (Proposed Well)


Pad Location: NWNE Section 32, T8S, R18E, S.L.B.&M.



SURVEYED BY:	K.S.	DATE SURVEYED:	06-21-11	VERSION:
DRAWN BY:	F.T.M.	DATE DRAWN:	08-05-11	\/1
SCALE: 1"	= 60'	REVISED:		VI

ackslash Tri State (4.35) 781–25Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078



From: Jim Davis

To: Hill, Brad; Mason, Diana

CC: Bonner, Ed; Garrison, LaVonne; mcrozier@newfield.com; teaton@newfield...

**Date:** 9/20/2011 3:45 PM **Subject:** Newfield APD approvals

The following APDs have been approved by SITLA including arch and paleo clearance.

4304751877 GMBU I-32-8-18 4304751878 GMBU H-32-8-18 4304751879 GMBU L-32-8-18 4304751880 GMBU R-32-8-18 4304751881 GMBU M-32-8-18 4304751882 GMBU G-32-8-18 4304751883 GMBU N-32-8-18 4304751884 GMBU S-32-8-18 4301350898 GMBU 1-2-9-15H 4301350906 GMBU R-2-9-15 4301350907 GMBU L-2-9-15 GMBU H-2-9-15 4301350908 4301350909 GMBU M-2-9-15 GMBU N-2-9-15 4301350910 4301350911 GMBU Q-2-9-15 Thanks.

Thank:

Jim Davis Utah Trust Lands Administration jimdavis1@utah.gov Phone: (801) 538-5156


**RECEIVED:** September 20, 2011

# BOPE REVIEW NEWFIELD PRODUCTION COMPANY GMBU H-32-8-18 43047518780000

Well Name												
NEW ILLE PRODUCTION COMPT					IPANY	GMBU I	H-32	2-8-18 4304				
String		SURF	4	PROD								
Casing Size(")		8.625	Щ	5.500			<u></u>					
Setting Depth (TVD)	300		6420									
Previous Shoe Setting Dept	0		300									
Max Mud Weight (ppg)		8.3	Ī	8.4								
BOPE Proposed (psi)	500	T	2000									
Casing Internal Yield (psi)	2950	Ī	4810									
Operators Max Anticipate	d Pressure (psi)	2780	Ī	8.3								
Calculations	SUR	F String				8.625	5 "	•				
Max BHP (psi)		.052*Setti	ing	g Depth*MW	129	)	j					
							В	BOPE Ade	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	x BHP-(0.12*	*S	etting Depth)=	93			YES	air drill			
MASP (Gas/Mud) (psi)	Max	x BHP-(0.22*	*S	etting Depth)=	63		j [	YES	ОК			
							*	Can Full	Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previo	us	Shoe Depth)	63			NO				
Required Casing/BOPE Te	est Pressure=				300	)	p	osi				
*Max Pressure Allowed @	Previous Casing Shoe=				0		p	psi *Assumes 1psi/ft frac gradient				
Calculations	PRO	D String				5.500	0 "	•				
Max BHP (psi)	.052*Setti	052*Setting Depth*MW=				ī						
							В	BOPE Ade	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	Max BHP-(0.12*Setting Depth)=				34		NO				
MASP (Gas/Mud) (psi)	Max	x BHP-(0.22*	*S	etting Depth)=	139	)2		YES	ОК			
							*	Can Full	Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previo	us	Shoe Depth)	145	i8		NO	Common in area			
Required Casing/BOPE To	est Pressure=				200	00	jp	osi				
*Max Pressure Allowed @	Previous Casing Shoe=				300	)	p	osi *Assı	umes 1psi/ft frac gradient			
Calculations	S	tring					٦,,	•				
Max BHP (psi)		.052*Setti	ing	g Depth*MW	┢		╬					
			_		+-		B	BOPE Ade	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	x BHP-(0.12*	*S	etting Depth)=	┢		怔	NO				
MASP (Gas/Mud) (psi)	Max	x BHP-(0.22*	*S	etting Depth)=	F			NO				
					1-				Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previo	us	Shoe Depth)				NO	I			
Required Casing/BOPE Te	est Pressure=				T			osi				
*Max Pressure Allowed @	Previous Casing Shoe=						p	osi *Assı	umes 1psi/ft frac gradient			
Calculations	S	tring	_					,				
Max BHP (psi)					〒		計					
					1-		B	BOPE Ade	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	x BHP-(0.12*	*S	etting Depth)=			7/2	NO				
MASP (Gas/Mud) (psi)				etting Depth)=	<u> </u>			NO				
, ", <b>u</b> " /			_	5 1.9	1		-1 1-		Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting December 1)	epth - Previo	us	Shoe Depth)=			712	NO	1			
Required Casing/BOPE Te		<u> </u>	_		⊭		= -	osi	1			
Required Cashig/DOTE Test Tressure							$     _{P}$					

\*Max Pressure Allowed @ Previous Casing Shoe= psi \*Assumes 1psi/ft frac gradient

# 43047518780000 GMBU H-32-8-18



Well name:

43047518780000 GMBU H-32-8-18

Operator:

**NEWFIELD PRODUCTION COMPANY** 

String type:

Surface

Project ID:

43-047-51878

Location:

**UINTAH** 

COUNTY

Minimum design factors: **Environment:** 

Collapse

Mud weight:

Design parameters:

8.330 ppg

Design is based on evacuated pipe.

Collapse:

Design factor 1.125

H2S considered? Surface temperature:

No 74 °F

Bottom hole temperature: Temperature gradient:

78 °F 1.40 °F/100ft

Minimum section length:

100 ft

Burst:

Design factor

1.00

Cement top:

80 ft

<u>Burst</u>

Max anticipated surface

No backup mud specified.

Load

(psi)

130

Seq

1

pressure: Internal gradient: 264 psi

Calculated BHP

300 psi

Design

**Factor** 

10.557

0.120 psi/ft Tension: 8 Round STC:

8 Round LTC:

Buttress:

Premium:

Body yield:

Load

(psi)

300

1.60 (J) 1.50 (J)

1.50 (B)

Design

Factor

9.83

1.80 (J)

1.70 (J)

Tension is based on air weight.

Neutral point: 262 ft

Non-directional string.

Re subsequent strings:

Next setting depth: Next mud weight:

6.420 ft 8.400 ppg 2,801 psi

Design

**Factor** 

33.90 J

Next setting BHP: Fracture mud wt: Fracture depth: Injection pressure:

Load

(kips)

7.2

19.250 ppg 300 ft 300 psi

Run Segment Nominal End True Vert Measured Drift Est. Sea Length Size Weight Grade **Finish** Depth Depth Diameter Cost (in) (ft) (lbs/ft) (ft) (ft) (in) (\$) 300 8.625 24.00 J-55 ST&C 300 300 7.972 1544 1 Collapse Collapse Collapse **Burst** Burst **Burst** Tension **Tension Tension** Run

Strength

(psi)

2950

Helen Sadik-Macdonald Prepared Div of Oil, Gas & Mining

Strength

(psi)

1370

Phone: 801 538-5357 FAX: 801-359-3940

Date: October 26,2011 Salt Lake City, Utah

Strength

(kips)

244

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:

43047518780000 GMBU H-32-8-18

Minimum design factors:

Operator:

**NEWFIELD PRODUCTION COMPANY** 

Production

Project ID:

String type:

43-047-51878

Location:

**UINTAH** COUNTY

**Environment:** 

Collapse

Mud weight:

Design parameters:

Collapse: Design factor

H2S considered? 1.125

Surface temperature:

Nο 74 °F

8.400 ppg Design is based on evacuated pipe.

Bottom hole temperature: Temperature gradient:

164 °F 1.40 °F/100ft

Minimum section length:

100 ft

Burst:

Design factor

1.00 Cement top: 861 ft

**Burst** 

Max anticipated surface

No backup mud specified.

pressure:

1,389 psi

Internal gradient: Calculated BHP

0.220 psi/ft

2,801 psi

**Tension:** 8 Round STC:

8 Round LTC: Buttress:

Premium:

Body yield:

1.60 (J) 1.50 (J)

1.80 (J)

1.80 (J)

1.60 (B)

Directional Info - Build & Hold

Kick-off point Departure at shoe:

600 ft 1239 ft 1.5 °/100ft

Maximum dogleg: Inclination at shoe:

12.96°

Tension is based on air weight.

Neutral point:

5.720 ft

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Cost (\$)
1	6557	5.5	15.50	J-55	LT&C	6420	6557	4.825	23153
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load (psi)	Strength (psi)	Design Factor	Load (psi)	Strength (psi)	Design Factor	Load (kips)	Strength (kips)	Design Factor
1	2801	4040	1.442	2801	4810	1.72	99.5	217	2.18 J

Prepared

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357

FAX: 801-359-3940

Date: October 26,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 6420 ft, a mud weight of 8.4 ppg The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a



#### VIA ELECTRONIC DELIVERY

November 8, 2011

State of Utah, Division of Oil, Gas and Mining ATTN: Diana Mason P.O. Box 145801 Salt Lake City, UT 84114-5801

RE: Directional Drilling

GMBU H-32-8-18

Greater Monument Butte (Green River) Unit

Surface Hole: T8S-R18E Section 32: NWNE (ML-22058)

685' FNL 1835' FEL

At Target: T8S-R18E Section 32: SENW (ML-22058)

1598' FNL 2618' FWL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing by Newfield Production Company ("NPC") of an Application for Permit to Drill the above referenced well dated 8/16/2011, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing preexiting roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4153 or by email at <a href="mailto:pburns@newfield.com">pburns@newfield.com</a>. Your consideration in this matter is greatly appreciated.

Sincerely,

Newfield Production Company


Peter Burns Land Associate

# STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

F	0	R	M	3

AMENDED REPORT [ ] (highlight changes)

											it changes)		
	4	APPLICAT	ION FOR	PE	ERMIT TO	D DRILL			5. MINERAL LEASE ML-22058	NO:	6. SURFACE: State		
1A. TYPE OF WORK: DRILL  REENTER DEEPEN D										7. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA			
B. TYPE OF WELL: OIL  GAS OTHER SINGLE ZONE  MULTIPLE ZONE  Greate											NAME: nt Butte		
2. NAME OF OP									9. WELL NAME and	NUMBER	:		
	roduction C	ompany		_					GMBU H-				
3. ADDRESS OF Route #3 E	3630 Box	<sub>CITY</sub> Myton	ST	ATE	JT <sub>ZIP</sub> 84	052	PHONE NUMBER: (435) 646-3721		10. FIELD AND POO	Butte	secret second ed		
	WELL (FOOTAGE	/5	0000000		00 <b>T</b> 00 D	405			11. QTR/QTR, SEC MERIDIAN:	TION, TOV	WISHIP, RANGE,		
AT SURFACE:		685' FNL 18					'00 D40E		NWNE 32	88	18E		
AT PROPOSEI	O PRODUCING ZO	NE: SE/INVV	1598, EN	L 20	18. FWL	Sec. 32 T	85 K18E						
		CTION FROM NEAF							12. COUNTY:		13. STATE: UTAH		
		niles southe		, Ut					Uintah				
		e, NA' f/unit l	0.00	1	16. NUMBER O	F ACRES IN LEA		17. NO	JMBER OF ACRES A	SSIGNED			
		(DRILLING, COMPL		-	19. PROPOSED	DEPTH-	640.00 acres	20 BC	OND DESCRIPTION:		20 acres		
APPLIED FOR	R) ON THIS LEASE	(FEET)		- 1			6,557	-	#B001834				
		R DF, RT, GR, ETC.	):	7	22. APPROXIMA	ATE DATE WORK		23. ES	TIMATED DURATION				
4977' GL					エサ	Ortr.	2011	(15	i) days from S	PUD f	to rig release		
24. PROPOSED CASING AND CEMENTING PROGRAM													
SIZE OF HOLE	CASING SIZE,	GRADE, AND WEIGI	T PER FOOT	SET	TING DEPTH		CEMENT TYPE, QU.	ANTITY, '	YIELD, AND SLURRY	WEIGHT			
12 1/4	8 5/8	J-55	24.0		300	Class G w	ı/2% CaCl	138 s	sx +/-	1.17	15.8		
7 7/8	5 1/2	J-55	15.5		6,557	Lead(Prer	m Lite II)	315 sx +/-		3.26	11.0		
							) Poz)	363 s	sx +/-	1.24	14.3		
				_									
25.					ATTA	HMENTS							
VERIFY THE FOL	LOWING ARE ATT.	ACHED IN ACCORD	ANCE WITH THE L	ЛАН (	DIL AND GAS CO	NSERVATION G	ENERAL RULES:						
<b>✓</b> WELL PLA	AT OR MAP PREPA	ARED BY LICENSED	SURVEYOR OR E	NGINE	:FR	✓ con	MPLETE DRILLING PLAN						
							RM 5, IF OPERATOR IS PE	DDON OF	CONDANY OTHER	T. IAAI T. ()	- 1 - 4 0 - 0 0 4 1 - 0		
<b>▼</b> EAIDEMC	E OF DIVISION OF	WATER RIGHTS AF	PROVAL FOR US	EUFV	VALER		IM 3, IF OPERATOR IS PE	YSUN UF	COMPANY OTHER	THAN THE	: LEASE OVVNER		
						-							
NAME (PLEASE P	RINT) Mandie	Crozier	-A			TITLE	Regulatory Sp	ecialis	st				
SIGNATURE	N ko	melio	Crosi	2		DATE	8/16/	U					
This space for State	e use only)		0					-					
API NUMBER ASS	IGNED:			_	-	APPROVAL:							



PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



DRAWN BY:

DATE:

SCALE

P: (435) 781-2501 F: (435) 781-2518

📤 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

C.H.M. REVISED: VERSION 08-03-2011 1"= 2,000



# **NEWFIELD EXPLORATION COMPANY**

31-32-8-18 (Existing Well) H-32-8-18 (Proposed Well) I-32-8-18 (Proposed Well) SEC. 32, T8S, R18E, S.L.B.&M. Uintah County, UT.

TOPOGRAPHIC MAP

SHEET В

### **ON-SITE PREDRILL EVALUATION**

### Utah Division of Oil, Gas and Mining

**Operator** NEWFIELD PRODUCTION COMPANY

Well Name GMBU H-32-8-18

**API Number** 43047518780000 **APD No** 4458 **Field/Unit** EIGHT MILE FLAT

**Location: 1/4,1/4** NWNE **Sec** 32 **Tw** 8.0S **Rng** 18.0E 685 FNL 1835 FEL

GPS Coord (UTM) Surface Owner

#### **Participants**

M. Jones (UDOGM), T. Eaton (Newfield).

#### Regional/Local Setting & Topography

This proposed well is staked on an existing well location for the 31-32-8-18 well. No additional pad disturbance is anticipated for the location. The old pit area will be utililized. The topography surrounding the location is rolling, gravely, low sage hills. With dry wash drainages running in various directions throughout the area. The site is approximately 18 road miles southeast Myton, Utah.

#### Surface Use Plan

**Current Surface Use** 

Grazing Wildlfe Habitat Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

Width 111 Length 303 Onsite

**Ancillary Facilities** 

#### **Waste Management Plan Adequate?**

#### **Environmental Parameters**

Affected Floodplains and/or Wetlands N

Flora / Fauna

Existing pad.

**Soil Type and Characteristics** 

gravely clay

**Erosion Issues** N

**Sedimentation Issues** N

Site Stability Issues N

**Drainage Diverson Required?** N

Berm Required? Y

Berm location to prevent spills from leaving and runoff from entering location.

11/8/2011 Page 1

**Erosion Sedimentation Control Required?** N

Paleo Survey Run? Y Paleo Potental Observed? N Cultural Survey Run? Y Cultural Resources? N

#### **Reserve Pit**

Site-Specific Factors	Site R		
Distance to Groundwater (feet)	>200	0	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
<b>Drill Cuttings</b>	Normal Rock	0	
<b>Annual Precipitation (inches)</b>		0	
Affected Populations			
<b>Presence Nearby Utility Conduits</b>	Not Present	0	
	Final Score	35	1 Sensitivity Level

#### **Characteristics / Requirements**

Dugout earthen (80' x 40' x 8').

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? N

#### **Other Observations / Comments**

Evaluator	Date / Time
Mark Jones	8/31/2011

11/8/2011 Page 2

# **Application for Permit to Drill Statement of Basis**

11/8/2011 Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo				Status		Well Type	<b>Surf Owner</b>	<b>CBM</b>
4458	43047518780	000			LOCKE	ED	OW	S	No
Operator	NEWFIELD PRODUCTION COMPANY				COMPAN	Surface Owner-APD			
Well Name	GMBU H-32-	-8-18					Unit	GMBU (GRF	RV)
Field	EIGHT MILE	E FLA	ΛT				Type of Work	DRILL	
Location	NWNE 32	8S	18E	S	685 FNL	1835 FEL	GPS Coord (UTM)	592559E 4437	7186N

#### **Geologic Statement of Basis**

Newfield proposes to set 300' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 200'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 32. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be an interconnected, high volume source of useable ground water. The proposed surface casing should adequately protect useable ground water in this area.

Brad Hill 9/27/2011
APD Evaluator Date / Time

#### **Surface Statement of Basis**

This proposed well is staked on an existing well location for the 31-32-8-18 well. No additional pad disturbance is anticipated for the location. The old pit area will be utililized. The topography surrounding the location is rolling, gravely, low sage hills. With dry wash drainages running in various directions throughout the area. The site is approximately 18 road miles southeast Myton, Utah. A 16 mil synthetic liner will be required lining the reserve pit. Maintain berms around pad. Fence reserve pit upon completion of drilling.

Mark Jones 8/31/2011
Onsite Evaluator Date / Time

#### **Conditions of Approval / Application for Permit to Drill**

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

**RECEIVED:** November 08, 2011

#### WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 8/16/2011 **API NO. ASSIGNED:** 43047518780000

WELL NAME: GMBU H-32-8-18

**OPERATOR:** NEWFIELD PRODUCTION COMPANY (N2695) **PHONE NUMBER:** 435 646-4825

**CONTACT:** Mandie Crozier

PROPOSED LOCATION: NWNE 32 080S 180E **Permit Tech Review:** 

> **SURFACE:** 0685 FNL 1835 FEL **Engineering Review:**

> **BOTTOM:** 1598 FNL 2618 FWL Geology Review:

**COUNTY: UINTAH** 

**LATITUDE: 40.07986 LONGITUDE:** -109.91440 UTM SURF EASTINGS: 592559.00 **NORTHINGS: 4437186.00** 

FIELD NAME: EIGHT MILE FLAT

LEASE TYPE: 3 - State

**LEASE NUMBER: ML-22058** PROPOSED PRODUCING FORMATION(S): GREEN RIVER **SURFACE OWNER:** 3 - State **COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

✓ PLAT R649-2-3.

Unit: GMBU (GRRV) **Bond: STATE - B001834** 

**Potash** R649-3-2. General

Oil Shale 190-5

**Oil Shale 190-3** R649-3-3. Exception

**Drilling Unit** Oil Shale 190-13

Board Cause No: Cause 213-11 Water Permit: 437478

**Effective Date:** 11/30/2009 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

**Intent to Commingle** ▼ R649-3-11. Directional Drill

**Commingling Approved** 


**Comments:** Presite Completed

Stipulations: 5 - Statement of Basis - bhill

15 - Directional - dmason

25 - Surface Casing - ddoucet 27 - Other - bhill

API Well No: 43047518780000



### State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

#### **Permit To Drill**

\*\*\*\*\*\*

**Well Name:** GMBU H-32-8-18 **API Well Number:** 43047518780000

**Lease Number:** ML-22058 **Surface Owner:** STATE **Approval Date:** 11/8/2011

#### **Issued to:**

NEWFIELD PRODUCTION COMPANY, Rt 3 Box 3630, Myton, UT 84052

#### **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### **Conditions of Approval:**

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Surface casing shall be cemented to the surface.

#### **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

API Well No: 43047518780000

#### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

#### **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

#### **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas

### BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 29 Submitted By Branden Arnold Phone Number 435-401-0223 Well Name/Number GMBU H-32-8-18 Qtr/Qtr NW/NE Section 32 Township 8S Range 18E Lease Serial Number ML-22058 API Number 43-047-51878
<u>Spud Notice</u> – Spud is the initial spudding of the well, not drilling out below a casing string.
Date/Time <u>7/11/12</u> <u>8:00</u> AM ⊠ PM □
Casing − Please report time casing run starts, not cementing times.  Surface Casing Intermediate Casing Production Casing Liner Other
Date/Time <u>7/11/12</u> <u>4:00</u> AM ☐ PM ⊠
BOPE Initial BOPE test at surface casing point BOPE test at intermediate casing point 30 day BOPE test Other  Date/Time AM PM
Remarks

OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630

OPERATOR ACCT. NO.

N2695

MYTON, UT 84052

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	- 00	WE SC	LL LOCAT		COUNTY	SPUD DATE	EFFECTIVE DATE
В	99999	17400	4301351114	GMBU L-6-9-16	SENE	6	98		DUCHESNE	7/19/2012	7131112
WELL 1 COMMENTS:  CRRV BHL: NWSe											
ACTION	CURRENT	NEW	API NUMBER	WELL NAME	QQ	WE SC	LL LOCAT	ION RG	COUNTY	SPUD DATE	EFFECTIVE
A	99999 99999	ISUSH	4304751333	UTE TRIBAL 14-28-4-2E	SESW	28		2E	UINTAH	7/10/2012	7/3/12
ىنا	STC									-	
ACTION B	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	ao	SC WE	LL LOÇAT		COUNTY	SPUD DATE	EFFECTIVE
Α	99999	18635	4304752020	UTE TRIBAL 5-12-4-1E	SWNW	12	48	1E	UINTAH	7/13/2012	7131112
سا	STC	*									IAL
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	QQ	WE SC	LL LOCAT	ION RG	COUNTY	SPUD DATE	EFFECTIVE DATE
В	99999	17400	4304751878	GMBU H-32-8-18	NWNE	32	85	18E	UINTAH	7/12/2012	7131112
GR	RV BHI	_: Ser	w.							A	
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	QQ	WE SC	LL LOCAT	ION RG	COUNTY	SPUD DATE	EFFECTIVE DATE
В	99999	17400	4304751877	GMBU I-32-8-18	NWNE	32	88		UINTAH	7/11/2012	7131112
Cat	RV P	HL: C	6 L 0								
ACTION	CURRENT	NEW	API NUMBER	WELL NAME	WELL LOCATION  QQ SC TP RG C			COUNTY	SPUD DATE	EFFECTIVE DATE	
CODE	99999	17400	4301350458	GMBU R-19-8-17	NWSE	19	85		DUCHESNE	6/27/2012	7/21/12
			wse		.1						
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	ga	SC WE	LL LOCAT	ION RG	COUNTY	SPUD DATE	EFFECTIVE DATE
Α	99999	18636	4301350655	UTE TRIBAL 14-3-4-4W	SESW	3	.4S		DUCHESNE	6/25/2012	7 131 112
8-	new entity for new well (single well to existing entity (group or rom one existing entity to anoth	unit well)	びらて	RECEIVED			IAL	, \	Signature	phot	Tabitha Timothy
D- v	well from one existing entity to anoth well from one existing entity to a her (explain in comments section	a new entity		JUL 2 3 2012	-				Production Clerk		07/19/12

	5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-22058			
SUNDRY	NOTICES AND REPO	ORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	ill new wells, significantly deepen existing wells b al laterals. Use APPLICATION FOR PERMIT TO			7. UNIT OF CA AGREEMENT NAME: GMBU
1. TYPE OF WELL: OIL WELL			on proposition	8. WELL NAME and NUMBER: GMBU H-32-8-18
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COM	(PANY			9. APINUMBER: 4304751878
3. ADDRESS OF OPERATOR:			PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:
Route 3 Box 3630	CITY Myton STATE UT	ZIP 84052	435.646.3721	GREATER MB UNIT
4. LOCATION OF WELL: 695 FOOTAGES AT SURFACE:	FNL 1835 FEL			COUNTY: UINTAH
OTR/OTR. SECTION. TOWNSHIP. RANGE.	MERIDIAN: , 32, T8S, R18E			STATE: UT
CHECK APPROD	PRIATE BOXES TO INDICAT	E NATURE	OF NOTICE, REP	ORT, OR OTHER DATA
TYPE OF SUBMISSION		TY	PE OF ACTION	
	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION
NOTICE OF INTENT (Submit in Duplicate)	ALTER CASING	FRACTURE	TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will	CASING REPAIR	ASING REPAIR NEW CONSTRUCTION		TEMPORARITLY ABANDON
	CHANGE TO PREVIOUS PLANS	OPERATOR	CHANGE	TUBING REPAIR
	CHANGE TUBING	PLUG AND	ABANDON	VENT OR FLAIR
X SUBSEQUENT REPORT	CHANGE WELL NAME	PLUG BACK		WATER DISPOSAL
(Submit Original Form Only)	CHANGE WELL STATUS	PRODUCTIO	ON (START/STOP)	WATER SHUT-OFF
Date of Work Completion:	COMMINGLE PRODUCING FORMATIONS	RECLAMAT	ION OF WELL SITE	X OTHER: - Spud Notice
07/13/2012	CONVERT WELL TYPE	RECOMPLE	TE - DIFFERENT FORMATION	_
On 7/12/12 MIRU Ross #2	OMPLETED OPERATIONS. Clearly show 9. Spud well @8:00 AM. Drill 310' o to with 160 sks of class "G" w/ 2% C ent to pit. WOC.	f 12 1/4" hole v	with air mist. TIH W/	7 Jt's 8 5/8" J-55 24# csgn. Set @
				RECEIVED
				AUG 0 6 2012
			Di	V. OF OIL, GAS & MINING

DATE 07/18/2012

(This space for State use only)

NAME (PLEASE PRINT) Branden Arnold

## Casing / Liner Detail

Well	GMBU H	-32-8-18							
Prospect	Monumer	nt Butte							
Foreman									
Run Date:									
String Type	Surface, 8	3.625", 2		55, STC (Ger	neric)				
•	-a Three Paraget -b Americanska reskup- i b Par		na <sub>ng</sub> gunggangungunggaladas bir	- Detai	I From Top	To Bottom	-		
Depth	Length	JTS	S			Description		OD	ID
311.02			10	' KB		-			
311.60	1.42		W	ellhead					
313.02	-2.00	-1	Cı	utt Off				8.625	
10.00	259.40	6	8	5/8 Casing				8.625	
269.40	41.30	1	Sł	noe Joint				8.625	
310.70	0.90	1	G	uide Shoe				8.625	
311.60			-						
					Cement D	)etail			
Cement Comp					A place and the second				
Slurry # c	of Sacks   Wei	ight (ppg) 15.8	Yield 1.17	Volume (ft <sup>3</sup> ) 187.2	class G+2%k		tion - Slurry Class and Additive	es 	
Stab-In-Job?			No			Cem	nent To Surface?	Ye	s
BHT:			0			Est.	Top of Cement:	0	
Initial Circulation							s Bumped?	Ye	
Initial Circulation						<u>i</u>	ssure Plugs Bumped:	37	
Final Circulatio							ts Holding?	No	
Final Circulatio							ing Stuck On / Off Bottom?	No.	
Displacement F			/ater			L	ing Reciprocated?	. No	
Displacement I						ļ	ing Rotated?	No	
Displacement \	volume:		16.5			CIP:		11:	3U
Mud Returns:	- And DI						ing Wt Prior To Cement:		
Centralizer Typ				- F 4b		Cas	ing Weight Set On Slips:		
Middle of first,	top of second	and third f	or a total	or three.					

Sundry Number: 29833 API Well Number: 43047518780000

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES		FORM 9
ı	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22058		
SUNDR	Y NOTICES AND REPORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	posals to drill new wells, significantly deep reenter plugged wells, or to drill horizontal I n for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: GMBU H-32-8-18
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	DMPANY		<b>9. API NUMBER:</b> 43047518780000
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT		NE NUMBER: t	9. FIELD and POOL or WILDCAT: EIGHT MILE FLAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0685 FNL 1835 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NWNE Section: 3	HIP, RANGE, MERIDIAN: 32 Township: 08.0S Range: 18.0E Meridian:	s	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICATE NA	ATURE OF NOTICE, REPOR	T, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	☐ ACIDIZE ☐ A	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:		CHANGE TUBING	CHANGE WELL NAME
SUBSEQUENT REPORT		COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
Date of Work Completion:		RACTURE TREAT	☐ NEW CONSTRUCTION
		PLUG AND ABANDON	☐ PLUG BACK
SPUD REPORT Date of Spud:		RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
		SIDETRACK TO REPAIR WELL	L TEMPORARY ABANDON
✓ DRILLING REPORT		ENT OR FLARE	☐ WATER DISPOSAL
Report Date: 8/30/2012		SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	OTHER	OTHER:
	completed operations. Clearly show all pervas placed on production on 08, hours.		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 12, 2012
NAME (PLEASE PRINT) Jennifer Peatross	<b>PHONE NUMBER</b> 435 646-4885	TITLE Production Technician	
SIGNATURE	100 010 1000	DATE	
N/A		9/7/2012	

Sundry Number: 30819 API Well Number: 43047518780000

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE		FORM 9
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22058		
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly reenter plugged wells, or to drill horizo n for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: GMBU H-32-8-18
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	9. API NUMBER: 43047518780000		
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT	, 84052 435 646-482	PHONE NUMBER: 5 Ext	9. FIELD and POOL or WILDCAT: EIGHT MILE FLAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0685 FNL 1835 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSI Qtr/Qtr: NWNE Section: 3	HIP, RANGE, MERIDIAN: 32 Township: 08.0S Range: 18.0E Meri	dian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
✓ DRILLING REPORT	TUBING REPAIR		☐ WATER DISPOSAL ☐
Report Date: 8/30/2012	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
0,00,20.2	WILDCAT WELL DETERMINATION	OTHER	OTHER:
The above well w	completed operations. Clearly show vas placed on production on oduction Start Sundry re-se	n 08/30/2012 at 18:00	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 09, 2012
NAME (PLEASE PRINT) Kaci Deveraux	<b>PHONE NUME</b> 435 646-4867	BER TITLE Production Technician	
SIGNATURE		DATE 10/7/2012	
N/A		10/7/2012	

Sundry Number: 30819 API Well Number: 43047518780000

ח	STATE OF UTAH DEPARTMENT OF NATURAL RESOUR IVISION OF OIL, GAS, AND MI	CES INING	5.LEASE ML-220	FORM 9  DESIGNATION AND SERIAL NUMBER: 058
	6. IF IND	AN, ALLOTTEE OR TRIBE NAME:		
o not use this form for prop	y NOTICES AND REPORTS  posals to drill new wells, significantly elementer plugged wells, or to drill horize	doopon evieting	vells below APPLICATION GMBU (	r CA AGREEMENT NAME: GRRV)
TYPE OF WELL	for such proposals.		8. WELL	NAME and NUMBER: H-32-8-18
Oil Well  NAME OF OPERATOR:	MOANY		<b>9. API NI</b> 43047	JMBER: 518780000
ADDRESS OF OPERATOR:		PHONE NUMBER: 25 Ext	9. FIELD EIGHT	and POOL or WILDCAT: MILE FLAT
Rt 3 Box 3630 , Myton, UT, LOCATION OF WELL FOOTAGES AT SURFACE:	04032		COUNT	
0685 FNL 1835 FEL	il <mark>P, RANGE, MERIDIAN:</mark> 22 Township: 08.0S Range: 18.0E Me	eridian: S	STATE: UTAH	
ı. CHEC	APPROPRIATE BOXES TO INDIC	ATE NATURE OF	NOTICE, REPORT, OR (	OTHER DATA
TYPE OF SUBMISSION		TYPE	OF ACTION	
NOTICE OF INTENT Approximate date work will start:  SUBSEQUENT REPORT Date of Work Completion:  SPUD REPORT Date of Spud:  ✓ DRILLING REPORT Report Date: 8/30/2012  12. DESCRIBE PROPOSED OF The above well w	CHANGE TO PREVIOUS PLANS  CHANGE WELL STATUS  DEEPEN  OPERATOR CHANGE  ✓ PRODUCTION START OR RESUME  REPERFORATE CURRENT FORMATION  TUBING REPAIR  WATER SHUTOFF  WILDCAT WELL DETERMINATION  R COMPLETED OPERATIONS. Clearly shews	FRACTURE TREA  PLUG AND ABAN  RECLAMATION O  SIDETRACK TO R  VENT OR FLARE  SI TA STATUS E)  OTHER	TON CON CONTROL CONTRO	CHANGE WELL NAME  CONVERT WELL TYPE  NEW CONSTRUCTION  PLUG BACK  RECOMPLETE DIFFERENT FORMATION  TEMPORARY ABANDON  WATER DISPOSAL  APD EXTENSION  THER:  Production Start Sundry
	PHONE N	UMBER TITLE		

#### **Daily Activity Report**

#### Format For Sundry GMBU H-32-8-18 6/1/2012 To 10/30/2012

8/18/2012 Day: 1

Completion

Rigless on 8/18/2012 - CBL, Pressure test, perf bottoms - RIH w/CBL tools. POOH logging out w/CBL tools. - Presurre test Csg valves, camerons and frac valves to a low of 300psi and a high of 4400psi. - Held safety meeting talked about PPE and over head wirline hazards. - RIH w/perf gun to shoot bottoms.SWIFN

Daily Cost: \$0

**Cumulative Cost:** \$22,402

8/21/2012 Day: 2

Completion

Rigless on 8/21/2012 - Flow Back Well & Set Kill plug - RU Flow back. Open @ 1817 psi. Flow back on 20 choke @ approx. 3 bpm. Recover 540 bbls. Pumped 1449 bbls. ( 909 BBLS LEFT TO RECOVER) SWI, SDFN - 1st stage RU BJ Safety Meeting JSA. Press test Lines to 5200 psi. Open Well @ 90 psi Break Down CP-4, CP-2, formation (18 holes) @ 3928 psi @ 4.1 BPM W/ 10 bbls Fresh water. Pump 10 bbls 15% HCL 186 bbls Fresh Water To get Rate, 15 BBls to get X link pump 129 bbls 2# to 4# 20/40 sand (ramped) 255 bbls 4# to 6# 20/40 sand (ramped), 96 bbls 6# 20/40 sand (6# Hold) 12 bbls 15% HCL, 140.3 bbls Fresh water Flush. ISIP 1602 psi, FG .70, Max Press 4060 psi, Avg Press 2958 psi, Max Rate 33.9 BPM Avg Rate 33.4 BPM. ( 85508# 20/40 White Sand in Formation) - Shut well in. RD BJ frac equip. RDMO - 2nd Stage RU Extreme WL & WFT Tester press test Lube to 5000psi. Open Well @ 1461 psi, RIH w/ CFTP & 3-1/8 Csg Guns 3 SPF set CFTP @ 4680' & perforate the GB-6, GB-4 & GB-2 Formation @ 4494'-95', 4539'-40, 4543'-44', 4598'-99', 4604'-05', 4606'-07', (18 holes) POOH RD WL CWI' - 2nd stage RU BJ Safety Meeting JSA. Press test Lines to 5200 psi. Open Well @ 1435 psi Break Down GB-6, GB-4, GB-2, formation (18 holes) @ 1941 psi @ 4 BPM W/ 1.2 bbls Fresh water. Pump 39 bbls Fresh Water To get Rate, 15 BBls to get X link pump 113 bbls 2# to 4# 20/40 sand (ramped) 217 bbls 4# to 6# 20/40 sand (ramped), 126 bbls 6# 20/40 sand (6# Hold), 107 bbls Fresh water Flush. ISIP 1961 psi, FG .86, Max Press 3734 psi, Avg Press 3231 psi, Max Rate 40.5 BPM Avg Rate 33.1 BPM. ( 80946# 20/40 White Sand in Formation)

Daily Cost: \$0

**Cumulative Cost:** \$107,799

#### 8/28/2012 Day: 3

Completion

WWS #5 on 8/28/2012 - MIRU, Test BOPE, Tally PU tbg. - Crew Travel - RU 4 Star press test unit, Test 2-2 7/16" gate valves, accumulators broke drive chain, switched out acc. Continue testing double pipes & TIW valve to 4300 psi. Test good. - Tally & PU tbg as follows: 4 3/4" concave chomp mill, pump off bit sub, 149-jts 2 7/8" tbg, tag sand @ 4665', 15' sand on plug, LD 2-jts tbg & circulate well clean, EOT @ 4603', RU power swivel, CWI & SDFN - MIRU, Unload tbg on pipe racks, ND frac frac valve, NU rig BOPs, Change out bind rams for double pipe rams, Check press on well, 100 psi, Bleed off well. - Crew Travel & Safety Meeting

Daily Cost: \$0

Cumulative Cost: \$129,698

#### 8/29/2012 Day: 4

Completion

WWS #5 on 8/29/2012 - Drill out plugs, Clean out to PBTD, Swab - Check press on well, csg

50 psi, tbg 25 psi, Tag sand @ 4655', Clean out to plug @ 4680', Drill out plug in 12 min, Cont. PU tbg & tag sand @ 6424', Clean out to PBTD @ 6520', Circ well clean, RD power swivel. LD 3-jts tbg, Eot @ 6442' - RU swab equip, Fluid @ surface, Made 15 swab runs, Trace oil & no sand, Recover 142 bbls fluid, FFL @ 2200', RD swab equip, CWI & SDFN - Crew Travel Crew Travel & Safety Meeting.

Daily Cost: \$0

Cumulative Cost: \$135,563

#### 8/31/2012 Day: 5

Completion

WWS #5 on 8/31/2012 - TOOH w/tbg, TIH w/ prod. Tbg, PU pump & rods. FINAL REPORT -Change over to rod equip, PU & prime rod pump, RIH w/ rod as follows: Pump (2 1/2"x1 3/4"x20x24 RHAC w/244" max stroke), 28-7/8" 8 per, 135-3/4" 4 per, 79-7/8" 4 per, 1-4" 7/8" sub, 1-2' 7/8" sub, 1 1/2" x 30' polish rod, seat pump, RU pumping unit, fill tbg w/ 3 bbls, stroke test pump to 800 psi, good pump action, stroke unit @ 5 strokes per min w/ 144" stroke, RDMO (END WATER 909 BBLS) - Crew Travel & Safety Meeting - Crew Travel - MU & RIH w/ prod.tbg as follows: 2 7/8" N/C, 2-jts 2 7/8" tbg, 2 7/8" PSN, 1-jt 2 7/8" tbg, 5 1/2" B-2C TAC, 193-its its 2 7/8" tbg. RD woork floor, ND BOPE, set TAC @ 6071', w/ 15000# tension, PSN @ 6105', EOT 6169', land on tbg hanger, NU wellhead. - Check press on well, on vac, PU 3-jts tbg & tag @ 6520' PBTD no fill, LD 12-jts tbg, TOOH w/ 196-jts tbg & BHA,

Finalized Daily Cost: \$0

**Cumulative Cost:** \$230,818

**Pertinent Files: Go to File List** 

Form 3160-4 (August 2007)

#### **UNITED STATES** DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB NO. 1004-0137 Expires: July 31, 2010

WELL (	COMP	LETION	OR RECOMPL	ETION RE	PORT A	AND LOG
--------	------	--------	------------	----------	--------	---------

	WI	ELL C	OMPL	ETIO	N OR F	RECOMPLE	ETIC	ON REP	ORT A	AND L	.OG			- 1	ase Ser	ial No.	
														ML-2	22058		
la. Type of V		<b>✓</b> O	il Well ew Well	G V	as Well Vork Over	Dry Deepen	O PI	ther lug Back	☐ Difi	f. Resvr.,				NA		Allottee or T	
			ther:												nit or C BU (GF		Name and No.
2. Name of NEWFIELD	Operator  O EXPLOF	RATION	и сомі	PANY												me and Well	No.
3. Address	1401 17TH S	T. SUITE	1000 DE	NVER. C	O 80202				Phone 1 35) 646	No. (incli	ude are	a code	)	9. Al	I Well 47-51	No.	
						lance with Fede	eral r							10. F	ield an	d Pool or Exp	loratory
At surface	e 685' FNI	& 183	35' FEL	(NW/N	IF) SEC	32, T8S, R18	RF (N	/II -22058	)					11 S	ec T	NT BUTTE R., M., on B	ock and
				(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,	0_, .00,	·- (··		,					s	urvey o	or Area SEC.	32, T8S, R18E
			7664			54' FEL (NW/I				•		•				or Parish	13. State
		FNL &	2 <del>029</del> i	WL (S	E/NW) S	EC. 32, T8S,	, R18						W	UIN	ГАН		UT
14. Date Spt 07/12/201:				Date T. /06/20	D. Reache	ed			te Com	pleted ()	8/30/2 Leady to					ns (DF, RKE 4987' KB	3, RT, GL)*
18. Total De		6555 6420	-		19. Pl	ug Back T.D.:	MD						idge Plug	Set:	MD IVD	1001 112	
21. Type El				gs Run	(Submit co	py of each)		S Way (SE			22. W	/as well	cored?	Z No		Yes (Submit	analysis)
						EUTRON,GR	R,CAI	LIPER, C	мт во	ND		as DS7	run? al Survey?	Z No □ No		Yes (Submit Yes (Submit	
23. Casing								Stage Ce	menter	l No.	of Sks.	&	Slurry	Vol.			
Hole Size 12-1/4"	Size/Gra 8-5/8" J-		Wt. (#/ft.)  24#	0	op (MD)	Bottom (M	D)	Dep		Туре	of Cen	nent	(BBI		Cem	ent Top*	Amount Pulled
7-7/8"	5-3/8 J-		5.5#	10	:	6543'				160 C					Surfac		
				1						460 50					Ouriac	,e	
						<u> </u>				<u> </u>							
24. Tubing	Record			<u> </u>						1							
Size	Depth S	Set (MD)		ker Dept	h (MD)	Size		Depth Set	(MD)	Packer	Depth (	MD)	Size		Dept	h Set (MD)	Packer Depth (MD)
2-7/8" 25. Producii	EOT@		TA @	6071'			- 2	26. Peri	foration	Record							
	Formation				ор	Bottom		Perfe	orated In				lize	No. H	oles		Perf. Status
A) Green (B)	River			4494'		6096'		4494-609	96'			.34"		33			
C)																	
D)																	
27. Acid, Fr			Cement S	queeze,	etc.					A		£ 1	[				
4494-6096	Depth Inter	vai	F	rac w/	166454#	# 20/40 white	sand	d and 964		Amount a							
										· 3· · · · · · · ·	,	,					
					-												
28. Producti	ion - Interva	ıl A															
Date First		Hours	Test		Oil	Gas	Wa		Oil Gra		Gas			ction M			
Produced	0/0/40	Tested	Prod	uction	BBL	MCF	BB		Corr. A	PI	Gra	ivity	2-1/2	2" x 1-3	/4" x 2	20' x 21' x 2	4' RHAC Pump
8/30/12 Choke	9/9/12 Tbg. Press.	24 Csg.	24 H	īr.	17 Oil	Gas	69 Wa		Gas/Oil		We	ll Statu	ıs				
		Press.	Rate		BBL	MCF	BB		Ratio			RODU					
28a. Produc				-													
Date First Produced	Test Date	Hours Tested	Test Prod	uction	Oil BBL	Gas MCF	Wa BB		Oil Gra Corr. A		Ga: Gra	s avity	Produ	iction M	ethod		
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 H Rate		Oil BBL	Gas MCF	Wa BB		Gas/Oil Ratio		We	ell Stati	ıs			RECEI	VED
3120	SI	. 1033.	Late	<b>→</b>		44404		<del>~</del>							(	OCT 2 4	2012

<sup>\*(</sup>See instructions and spaces for additional data on page 2)

						=			<del>.</del>		
	uction - Inte Test Date	rval C Hours	Test	Oil	Gas	Water	Oil Grav	/itv	Gas	Production Method	
Produced		Tested	Production	BBL	MCF	BBL	Corr. AF		Gravity	Todacion House	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio		Well Status		
28c. Prodi Date First Produced	Test Date	rval D Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Grav Corr. Al		Gas Gravity	Production Method	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio		Well Status		
29. Dispos	sition of Gas	s (Solid, u	sed for fuel, ve	ented, etc.	)						
USED FOR											
30. Sumn	nary of Poro	us Zones	(Include Aqu	ifers):					31. Formati	on (Log) Markers	
	ng depth int					intervals and al ng and shut-in			GEOLOG	ICAL MARKERS	
For	nation	Тор	Bottom		Desc	criptions, Conte	ents, etc.			Name	Top Meas. Depth
GREEN RI	VER	4494'	6096'						GARDEN GU GARDEN GU	JLCH MARKER JLCH 1	4067' 4239'
									GARDEN GU POINT 3 MA		4354' 4625'
									X MRKR Y MRKR		4846' 4884'
									DOUGLAS O BI-CARBON	CREEK MRKR ATE	5023' 5274'
									CASTLE PE BASAL CAR		5875' 6273'
				i					WASATCH		6395'
32. Addi	tional remar	ks (includ	e plugging pro	cedure):							
33. Indic	ate which it	ems have l	been attached	by placing	g a check in the	e appropriate b	oxes:				
		_	s (1 full set rec			Geologic Repo		DST Repo	ort	☑ Directional Survey	
34. I here	eby certify t	hat the for	egoing and att	tached inf	ormation is co	nplete and corr	rect as determ	nined from	all available	records (see attached instructions	)*
			ennifer Pea			· 			Technician		
	Signature	XI	atros	5				0/02/2012			
						it a crime for a			nd willfully to	o make to any department or agen	acy of the United States any

(Continued on page 3) (Form 3160-4, page 2)



### **NEWFIELD EXPLORATION**

USGS Myton SW (UT) SECTION 32 T8, R18 H-32-8-18

Wellbore #1

Design: Actual

### **Standard Survey Report**

10 October, 2012





Survey Report



Company:

NEWFIELD EXPLORATION

Project:

USGS Myton SW (UT)

Site:

**SECTION 32 T8, R18** 

Well: Wellbore: H-32-8-18

Design:

Wellbore #1 Actual

Local Co-ordinate Reference:

Well H-32-8-18

TVD Reference: MD Reference:

Database:

H-32-8-18 @ 4989.0ft (NDSI SS #2) H-32-8-18 @ 4989.0ft (NDSI SS #2)

True

North Reference: Survey Calculation Method:

Minimum Curvature

EDM 2003.21 Single User Db

Project

USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA

Map System: Geo Datum:

US State Plane 1983

North American Datum 1983

Map Zone:

System Datum:

Mean Sea Level

Utah Central Zone

Site

**SECTION 32 T8, R18** 

Site Position:

Lat/Long

Northing:

7,200,263.45 ft

Latitude:

40° 4' 35.740 N

From:

Easting:

2,067,256.45 ft

Longitude:

109° 58' 28.340 W

**Position Uncertainty:** 

0.0 ft

Slot Radius:

**Grid Convergence:** 

0.98°

H-32-8-18, SHL LAT: 40 04 47.34 LONG: -109 54 52.14

Well Position

+N/-S

0.0 ft

Northing:

7,201,729.21 ft

Latitude:

40° 4' 47.340 N

**Position Uncertainty** 

+E/-W

0.0 ft 0.0 ft Easting:

2,084,038.08 ft Wellhead Elevation:

4,989.0 ft

Longitude: **Ground Level:**  109° 54' 52.140 W

4,977.0 ft

	IGRF2010	7/21/2011	11.25	65.85	52,305
Magnetics Mode		ample Date	그 그 그들은 그렇게 그 살이 그는 그를 가는 것이 이 경험에 가장 하는 것이 되었다. 그는 것이 없는 것이 없었다.	P Angle (°)	Fleid Strength (nT)
Wellbore Wellbore	<b>: #1</b> Pour orași de parater de alaba <del>la</del> Monto de liberalită (pour parale)	en Namas Mallin var Gelike noch i dellagigen jungspeggeber i Som om stem Sellen i Namas mit in som sell i den der mass		Karangarora Japan Bariya ka Kasaka ya K	gi Na 1947 - Artigorio Relevi Legato Apelengago, filologia (n. 1946).

Design	Actual	and the second of the second o	Park Mada disease englis e endre englis.	i en en la martina de la estada d No en la entra de la estada de l		The second second
Audit Notes:						
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0	
Vertical Section	•	Depth From (TVD)	#N/-S	+E:W	Direction	A RANGO COMO AND A
		(n) ,	(ft)	(n)	(9)	
		0.0	0.0	0.0	221.44	e en an area area e e e e e e e e e e e e e e e

Sı	rvey.Program From To (ft) (ft)	Date 10/19/2012 Survey (Wellbore)	, Tool Name	Gescription	
	316.0 6,555.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Measured	and the second					7			And B
Depth (ft)	inclination (°)	Azimuth (°)	Vertical Depth > (ft)	+N/-5 (ft)		ection	Dogleg Rate (°/100ft)	Build Rate (*/100ft)	Turn Rate (°/100m)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
316.0	0.25	139.40	316.0	-0.5	0.4	0.1	0.08	0.08	0.00
346.0	0.22	139.40	346.0	-0.6	0.5	0.1	0.10	~0.10	0.00
377.0	0.26	133.60	377.0	-0.7	0.6	0.1	0.15	0.13	-18.71
407.0	0.35	147.60	407.0	-0.8	0.7	0.2	0.39	0.30	46.67
438.0	0.10	153.10	438.0	-0.9	0.8	0.2	0.81	-0.81	17.74
468.0	0.40	191.10	468.0	-1.1	8.0	0.3	1.09	1,00	126.67
499.0	1.10	229.10	499.0	-1.4	0.5	0.7	2.65	2.26	122.58
529.0	1.80	225.80	529.0	-1.9	0.0	1.4	2.35	2.33	-11.00
560.0	2.30	228.10	560.0	-2.6	-0.8	2.5	1.63	1.61	7.42
590.0	3.10	227.90	589.9	-3.6	-1.9	3.9	2.67	2.67	-0.67
621.0	3.20	225.10	620.9	-4.8	-3.1	5.6	0.59	0.32	-9.03
651.0	3.60	226.40	650.8	-6.0	-4.4	7.4	1.36	1.33	4.33



Survey Report



Company:

NEWFIELD EXPLORATION

Project: Site: USGS Myton SW (UT) SECTION 32 T8, R18

Well:

H-32-8-18

Wellbore: Design;

Wellbore #1 Actual Local Co-ordinate Reference:

Well H-32-8-18

TVD Reference: MD Reference:

Database:

H-32-8-18 @ 4989.0ft (NDSI SS #2) H-32-8-18 @ 4989.0ft (NDSI SS #2)

North Reference:

True

Survey Calculation Method:

ion:Method: Minimum Curvature

EDM 2003.21 Single User Db

Depth (ft) 681.0 712.0 742.0 773.0 803.0 833.0	inclination (°) 4.35 4.80 5.00	Azimuth (°) 226.85	Depth (ft)	*N-8	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
681.0 712.0 742.0 773.0 803.0 833.0	4.35 4.80 5.00	226.85	(n)	March Comments		CARL THE RESERVE TO COLUMN TO SHAPE	STATE OF THE PROPERTY OF		TOW .
712.0 742.0 773.0 803.0 833.0	4.80 5.00			(ft)	· (ft)	(ft)	_ (%100ft)	(°/100ft)	/(°/100ft)
742.0 773.0 803.0 833.0	5.00	000.00	680.8	-7.4	-5.9	9.5	2.50	2.50	1.50
773.0 803.0 833.0		229.30	711.7	-9.1	-7.8	11.9	1.58	1.45	7.90
803.0 833.0		226.10	741.6	-10.8	-9.6	14.5	1.13	0.67	-10.67
833.0	5.40	221.30	772.4	-12.8	-11.6	17.3	1.91	1.29	-15.48
	5.60	223.10	802.3	-15.0	-13.5	20.2	0.88	0.67	6.00
	5.90	220.00	832.1	-17.2	-15.5	23.2	1.44	1.00	-10.33
864.0	6.50	221.00	863.0	-19.8	-17.7	26.5	1.97	1.94	3.23
894.0	7.10	218.40	892.7	-22.5	-19.9	30.1	2.25	2.00	-8.67
925.0	7.50	218.80	923.5	-25.6	-22.4	34.0	1.30	1.29	1.29
956.0 986.0	7.40 7.40	220.80	954.2	-28.7	-25.0	38.0	0.90	-0.32	6.45
1,017.0	7.40 7.80	220.60 222.30	984.0 1,014.7	-31.6 -34.7	-27.5 -30.2	41.9	0.09	0.00	-0.67
						46.0	1.48	1.29	5.48
1,061.0	7.90	219.80	1,058.3	-39.2	-34.2	52.0	0.81	0.23	-5.68
1,105.0 1,148.0	8.20 8.10	220.40 218.90	1,101.9	-43.9	-38.1	58.1	0.71	0.68	1.36
1,146.0	8.20	220.90	1,144.4 1,188.0	-48.6 -53.4	-42.0 -46.0	64.2 70.5	0.55	-0.23	-3.49
1,236.0	8.20	219.90	1,186.0	-53.4 -58.2	-46.0 -50.1	70.5 76.7	0.68 0.32	0.23 0.00	4.55 -2.27
1,280.0	8.40	218.40	1,275.1						
1,280.0	8.60	218.40	1,275.1	-63.1 -68.1	-54.1 -58.2	83.1 89.6	0.67 0.55	0.45 0.45	-3.41 2.05
1,367.0	9.05	220.00	1,361.1	-73.2	-56.2 -62.4	96.2	1.08	1.05	2.05 1.63
1,411.0	9.30	220.50	1,404.5	-78.6	-66.9	103.2	0.60	0.57	1.14
1,455.0	9.90	222.10	1,447.9	-84.1	-71.8	110.5	1.49	1.36	3.64
1,499.0	10.40	222.45	1,491.2	-89.8	-77.0	118.3	1.14	1,14	0.80
1,543.0	10.70	223.20	1,534.5	-95.7	-82.5	126.3	0.75	0.68	1.70
1,586.0	11.80	224.90	1,576.6	-101.8	-88.3	134.7	2.67	2.56	3.95
1,630.0	12.40	223.60	1,619.7	-108.4	-94.7	143.9	1.50	1.36	-2.95
1,674.0	13.00	224.80	1,662.6	-115.3	-101.5	153.6	1.49	1.36	2.73
1,718.0	13.90	223.80	1,705.4	-122.6	-108.6	163.8	2.11	2.05	-2.27
1,761.0	14.50	223.60	1,747.1	-130.3	-115.9	174.4	1.40	1.40	-0.47
1,805.0	14.50	223.90	1,789.7	-138.2	-123.5	185.4	0.17	0.00	0.68
1,849.0	14.60	222.80	1,832.3	-146.3	-131.1	196.4	0.67	0.23	-2.50
1,893.0	14.70	222.40	1,874.8	-154.4	-138.6	207.5	0.32	0.23	-0.91
1,936.0	14.70	221.50	1,916.4	-162.6	-145.9	218.4	0.53	0.00	-2.09
1,980.0	14.50	221.40	1,959.0	-170.9	-153.3	229.5	0.46	-0.45	-0.23
2,024.0 2,068.0	14.30	219.90	2,001.6	-179.2	-160.4	240.5	0.96	-0.45	-3.41
2,068.0	14.20 14.10	220.00 221.50	2,044.3 2,086.9	-187.5 -195.6	-167.4 -174.4	251.3 262.1	0.23 0.86	-0.23 -0.23	0.23 3.41
2,155.0	14.00	221.97	2,128.6	-203.4	-181.3	272.5	0.35	-0.23	1.09
2,199.0 2,243.0	13.80 13.80	221.10 220.70	2,171.3 2,214.1	-211.3 -219.3	-188.3 -195.2	283.1	0.66	-0.45	-1.98
2,287.0	13.60	220.70	2,214.1	-219.3 -227.1	-195.2 -202.1	293.6 304.0	0.22 0.75	0.00 -0.45	-0.91 2.50
2,330.0	13.40	221.80	2,298.6	-234.6	-208.8	314.0	0.75	-0.47	0.00
2,374.0	13.20	221.60	2,341.5	-242.1					
2,418.0	13.10	220.60	2,341.5 2,384.3	-242.1 -249.7	-215.5 -222.1	324.1 334.2	0.47 0.56	-0.45 -0.23	-0.45 -2.27
2,462.0	12.90	220.30	2,427.2	-257.2	-228.5	344.0	0.48	-0.45	-0.68
2,506.0	12.80	221.50	2,470.1	-264.6	-234.9	353.8	0.65	-0.23	2.73
2,550.0	13.58	220.12	2,512.9	-272.2	-241.5	363.9	1.91	1.77	-3.14
2,594.0	13.50	220.30	2,555.7	-280.1	-248.1	374.2	0.21	-0.18	0.41
2,638.0	13.20	218.30	2,598.5	-287.9	-254.6	384.3	1.25	-0.68	-4.55
2,682.0	13.10	217.30	2,641.3	-295.8	-260.7	394,3	0.56	-0.23	-2.27
2,726.0	12.80	218.10	2,684.2	-303.6	-266.7	404.2	0.79	-0.68	1.82
2,769.0	12.70	219.90	2,726.2	-311.0	-272.7	413.6	0.95	-0.23	4.19
2,813.0	12.74	220.00	2,769.1	-318.4	-278.9	423.3	0.10	0.09	0.23



Survey Report



Company:

**NEWFIELD EXPLORATION** 

Project:

USGS Myton SW (UT)

Site:

**SECTION 32 T8, R18** 

Well: Wellbore: Design:

Wellbore #1

Actual

H-32-8-18

Local Co-ordinate Reference:

TVD Reference:

MD Reference: North Reference:

Well H-32-8-18

H-32-8-18 @ 4989.0ft (NDSI SS #2) H-32-8-18 @ 4989.0ft (NDSI SS #2)

True

**Survey Calculation Method:** 

Database:

Minimum Curvature

EDM 2003.21 Single User Db

22									
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
2,901,0	13.00	220.90	2,854.9	-333.3	-291.8	443.0	0.26	0.00	-1.14
2,944.0	13.20	221.40	2,896.7	-340.7	-298.2	452.8	0.53	0.47	1.16
2,988.0	13.30	221.40	2,939.6	-348.2	-304.9	462.8	0.23	0.23	0.00
3,032,0	13.20	220.60	2,982.4	-355.8	-311.5	472.9	0.47	-0.23	-1.82
3,076.0	12.74	219.50	3,025.3	-363.4	-317.9	482.8		-1.05	
3,120.0	12.74	218.50					1.19		-2.50
			3,068.2	-370.9	-323.9	492.4	0.74	-0.55	-2.27
3,163.0	12.40	218.50	3,110.2	-378.1	-329.7	501.7	0.23	-0.23	0.00
3,207.0	12.40	217.60	3,153.2	-385.6	-335.5	511.1	0.44	0.00	-2.05
3,251.0	12.70	216.80	3,196.1	-393.2	-341.3	520.6	0.79	0.68	-1.82
3,294.0	13.10	220.25	3,238.0	-400.7	-347.3	530.2	2.02	0.93	8.02
3,338.0	12.90	222.45	3,280.9	-408.1	-353.8	540.1	1.21	-0.45	5.00
3,381.0	12.90	222.30	3,322.8	-415.2	-360.3	549.7	0.08	0.00	-0.35
3,425.0	12.70	219.90	3,365.7	-422.5	-366.7	559.5	1.29	-0.45	-5.45
3,469.0	12.35	219.20	3,408.7	-429.9	-372.8	569.0	0.87	-0.80	-1.59
3,513.0	12.80	220.65	3,451.6	-437.2	-378.9	578.6	1.25	1.02	3.30
3,556.0	12.60	221.00	3,493.6	-437.2 -444.4					
			•		-385.1	588.0	0.50	-0.47	0.81
3,600.0	13.00	222.70	3,536.5	-451.7	-391.6	597.8	1.25	0.91	3.86
3,644.0	12.60	221.80	3,579.4	-458.9	-398.2	607.5	1.02	-0.91	-2.05
3,688.0	12.30	219.70	3,622.4	-466.1	-404.3	617.0	1.23	-0.68	-4.77
3,732.0	12.30	218.90	3,665.3	-473.3	-410.3	626.4	0.39	0.00	-1.82
3,776.0	12.70	220,40	3,708.3	-480.6	-416.4	635.9	1.17	0.91	3.41
3,819.0	12.80	220.20	3,750.2	-487.9	-422.5	645.4	0.25	0.23	-0.47
3,863.0	13.60	221.90	3,793.1	-495.5	-429.1	655.4	2.02	1.82	3.86
3,907.0	13.30	222.00	3,835.9	-503.1	-435.9	665.6	0.68	-0.68	0.23
3,951.0	12.80	221.75	3,878.7	-510.5	-442.6	675.6		-1.14	
3,995.0	12.50	221.73					1.14		-0.57
			3,921.7	-517.7	-449.0	685.2	0.72	-0.68	-1.02
4,038.0 4,082.0	13.00 12.70	223.95 223.70	3,963.6 4,006.5	-524.7 -531.7	-455.4 462.2	694.7 704.5	1.79	1.16	6.16
					-462.2		0.69	-0.68	-0.57
4,126.0	12.50	222.90	4,049.4	-538.7	-468.8	714.1	0.60	-0.45	-1.82
4,170.0	12.30	222.20	4,092.4	-545.7	-475.1	723.5	0.57	-0.45	-1.59
4,214.0	12.30	220.90	4,135.4	-552.7	-481.4	732.9	0.63	0.00	-2.95
4,257.0	12.40	222.20	4,177.4	-559.6	-487.5	742.1	0.69	0.23	3.02
4,301.0	12.30	222.50	4,220.4	-566.5	-493.8	751.5	0.27	-0.23	0.68
4,345.0	12.20	222.70	4,263.4	-573.4	-500.1	760.8	0.25	-0.23	0.45
4,389.0	12.50	223.10	4,306.4	-580.3	-506.5	770.2	0.71	0.68	0.91
4,432.0	12.30	222.40	4,348.4	-587.1	-512.8	779.5	0.58	-0.47	-1.63
4,476.0	12.90	221.80	4,391.3	-594.2 <b>←</b>		779.5 789.1	1.40	1.36	
4,476.0	13.40	220.90	4,391.3 4,434.2	-601.7	-519.2	789.1 799.1	1.40	1.36	-1.36 -2.05
4,564.0	13.40	221.90	4,477.0	-609.3					
4,564.0	13.40	223.10	4,477.0 4,519.7	-609.3 -616.9	-532.6 -539.5	809.3 819.6	0.53 0.93	0.00 0.68	2.27 2.73
4,651.0	13.50	221.70	4,561.5	-624.4	-546.4	829.7	0.90	-0.47	-3.26
4,695.0	13.00	222.20	4,604.4	-631.9	-553.1	839.8	1.17	-1.14	1.14
4,739.0	13.30	221.60	4,647.2	-639.4	-559.8	849.8	0.75	0.68	-1.36
4,783.0	12.80	221.50	4,690.1	-646.8	-566.4	859.7	1.14	-1.14	-0.23
4,826.0	13.10	221.20	4,732.0	-654.0	-572.7	869.4	0.71	0.70	-0.70
4,871.0	13.40	223.90	4,775.8	-661.6	-579.7	879.7	1.53	0.67	6.00
4,914.0	13.40	222.60	4,817.6	-668.9	-586.5	889.6	0.70	0.00	-3.02
4,958.0	13.60	221.00	4,860.4	-676.5	-593.4	899.9	0.96	0.45	-3.64
5,002.0	13.10	220.60	4,903.2	-684.2	-600.0	910.1	1.16	-1.14	-0.91
5,046.0	13.40	220.30	4,946.0	-691.9	-606.6	920.1	0.70	0.68	-0.68
5,090.0	12.90	220.80	4,988.9	-699.5	-613.1	930.1	1.17	-1.14	1,14
5,134.0	13.00	222.00	5,031.8	-706.9	-619.6	940.0	0.65	0.23	2.73
	13.00	219.00	5,073.7	-714.3	-625.9	949.7	1.57	0.00	-6.98
5,177.0									



Survey Report



Company:

**NEWFIELD EXPLORATION** 

Project: Site:

USGS Myton SW (UT) **SECTION 32 T8, R18** 

Well:

H-32-8-18

Wellbore: Design:

Wellbore #1 Actual

Local Co-ordinate Reference:

Well H-32-8-18

TVD Reference:

H-32-8-18 @ 4989.0ft (NDSI SS #2)

MD Reference: H-32-8-18 @ 4989.0ft (NDSI SS #2)

North Reference:

True

**Survey Calculation Method:** 

Minimum Curvature

Database:

EDM 2003.21 Single User Db


Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
5,265.0	12.50	217.80	5,159.5	-729.5	-637.9	969.1	0.70	-0.68	-0.68
5,308.0	12.60	217.70	5,201.4	-736.9	-643.6	978.4	0.24	0.23	-0.23
5,352.0	12.70	220.00	5,244.4	-744.4	-649.7	988.0	1.17	0.23	5.23
5,353.4	12.72	219.99	5,245.8	-744.7	-649.9	988.4	1.15	1.14	-0.71
H-32-8-18 T	ЭТ								
5,396.0	13.20	219.70	5,287.3	-752.0	-656.0	997.9	1.15	1.14	-0.68
5,440.0	13,50	222.50	5,330.1	-759.6	-662.7	1,008.1	1.62	0.68	6.36
5,484.0	13.10	220.50	5,372.9	-767.2	-669.4	1,018.2	1.39	-0.91	-4.55
5,527.0	13.50	221.50	5,414.7	-774.7	-675.9	1,028.1	1.07	0.93	2.33
5,571.0	13.80	221.90	5,457.5	-782.4	-682.8	1,038.5	0.71	0.68	0.91
5,614.0	13.30	220.30	5,499.3	-790.0	-689.4	1,048.5	1.45	-1.16	-3.72
5,658.0	13.90	221.20	5,542.1	-797.9	-696.2	1,058.9	1.45	1.36	2.05
5,702.0	14.80	222.90	5,584.7	-806.0	-703.5	1,069.8	2.26	2.05	3.86
5,745.0	14.55	221.50	5,626.3	-814.0	-710.8	1,080.7	1.01	-0.58	-3.26
5,789.0	14.30	221.70	5,668.9	-822.2	-718.1	1,091.6	0.58	-0.57	0.45
5,833.0	14.00	222.10	5,711.6	-830.2	-725.3	1,102.4	0.72	-0.68	0.91
5,877.0	13.40	221.30	5,754.3	-838.0	-732.2	1,112.8	1.43	-1.36	-1.82
5,921.0	13.20	221.10	5,797.1	-845.6	-738.9	1,122.9	0.47	-0.45	-0.45
5,964.0	12.70	221.70	5,839.0	-852.9	-745.2	1,132.6	1.20	-1.16	1.40
6,008.0	12.40	220.10	5,882.0	-860.1	-751.5	1,142.1	1.04	-0.68	-3.64
6,052.0	12.00	221.20	5,925.0	-867.1	-757.5	1,151.4	1.05	-0.91	2.50
6,096.0	11.80	220.40	5,968.1	-874.0	-763,5	1,160.5	0.59	-0.45	-1.82
6,139.0	11.50	220.90	6,010.2	-880.6	-769.1	1,169.2	0.74	-0.70	1.16
6,183.0	11.25	219.90	6,053.3	-887.2	-774.8	1,177.9	0.72	-0.57	-2.27
6,227.0	10.80	219.10	6,096.5	-893.7	-780.1	1,186.3	1.08	-1.02	-1.82
6,271.0	10.40	217.60	6,139.7	-900.0	-785.1	1,194.3	1.10	-0.91	-3.41
6,315.0	10.30	218.70	6,183.0	-906.3	-790.0	1,202.2	0.50	-0.23	2.50
6,358.0	10.40	220.80	6,225.3	-912.2	-795.0	1,210.0	0.91	0.23	4.88
6,402.0	10.00	220.90	6,268.6	-918.1	-800,1	1,217.7	0.91	-0.91	0.23
6,446.0	9.50	221.40	6,312.0	-923.7	-805,0	1,225.2	1.15	-1.14	1.14
6,490.0	9.40	221.40	6,355.4	-929.1	-809.7	1,232.4	0.23	-0.23	0.00
6,501.0	9.20	219.70	6,366.3	-930.5	-810.9	1,234.2	3.09	-1.82	-15.45
6,555.0	9.20	219.70	6,419.6	-937.1	-816.4	1,242.8	0.00	0.00	0.00

Checked By:	Approved By:	Date:	
Ondonou by.	/ Apploved by.		




Project: USGS Myton SW (UT) Site: SECTION 32 T8, R18


Well: H-32-8-18 Wellbore: Wellbore #1 Design: Actual



Azimuths to True North Magnetic North: 11.25°

Magnetic Field Strength: 52304.7snT Dip Angle: 65.85° Date: 7/21/2011 Model: IGRF2010





Design: Actual (H-32-8-18/Wellbore #1)

Created By: Sarah Well Date: 10:10, October 10 2012

THIS SURVEY IS CORRECT TO THE BEST OF MY KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA Sundry Number: 36879 API Well Number: 43047518780000

			FORM 9
	STATE OF UTAH		POKM 9
	DEPARTMENT OF NATURAL RESOUR DIVISION OF OIL, GAS, AND MII		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22058
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly reenter plugged wells, or to drill horize n for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: GMBU H-32-8-18		
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	9. API NUMBER: 43047518780000		
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 200	00 , Denver, CO, 80202	PHONE NUMBER: 303 382-4443 Ext	9. FIELD and POOL or WILDCAT: EIGHT MILE FLAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0685 FNL 1835 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NWNE Section:	HIP, RANGE, MERIDIAN: 32 Township: 08.0S Range: 18.0E Mer	idian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
☐ NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
✓ SUBSEQUENT REPORT	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion: 4/1/2013			
	OPERATOR CHANGE	PLUG AND ABANDON	L PLUG BACK
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
_	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	✓ OTHER	OTHER: Site Facility/Site Security
SEE ATT	COMPLETED OPERATIONS. Clearly show FACHED REVISED SITE FACIL		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 23, 2013
NAME (PLEASE PRINT) Jill L Loyle	<b>PHONE NUMB</b> 303 383-4135	BER TITLE Regulatory Technician	
SIGNATURE N/A	<u> </u>	DATE 4/22/2013	

Sundry Number: 36879 API Well Number: 43047518780000

